



यशोधरा गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय

बैदौली, कप्तिलवस्तु
लुम्बिनी प्रदेश, नेपाल

पत्र संख्या :- २०८१/८२ -

चलानी नम्बर :- ६९८


बैदौली, कप्तिलवस्तु
लुम्बिनी प्रदेश, नेपाल

मिति : २०८१/०७/१२

श्री सूचिकृत फार्म/कम्पनी सबै ।

विषय : कोटेशन/दररेट उपलब्ध गराइदिने सम्बन्धमा ।

प्रस्तुत विषयमा आर्थिक बर्ष ०८१।०८२ को स्वीकृत बार्षिक बजेट तथा कार्यक्रम अन्तरगत स्वास्थ्य चौकीहरूमा सोलर पावर ब्याकप जडानका लागि बजेट विनियोजन भएकोमा उक्त जडान कार्य गर्न कोटेशन माग गर्ने भनि मिति २०८१।०७।११ गते बसेको खरिद समितिबाट निर्णय भएकोले यस कार्यालयमा सो सँग सम्बन्धि कार्य गर्ने गरी सूचिकृत भएका फार्म/कम्पनीहरूले यो सूचनाको मितिले १० दिन भित्र यसै सूचना साथ संलग्न BOQ बमोजिम कोटेशन/दररेट उपलब्ध गराइदिनु हुन व्यहोरा अनुरोध छ ।


२०८१/०७/१२
(ऋषभ देव खनाल)

प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत

Office of Rural Municipal Executive



BILL OF MATERIALS

Yasodhara Rural Municipality
 Lalitpur, Nepal
 Baidauti, Kaptai, Nepal
 Lumbini Province, Nepal

[Signature]
 Chief Administrative Officer

Name of Work: Solar Backup System Installation
 Location: health post office

Item	Description	Quantity	Unit	Unit Price		Total Price (in NRS)
				In Figure	In Words	
1	Supply and fitting of Polycrystalline Solar Panel	2400	wp			
2	Supply and fitting of 2 KVA hybrid inverter	3	Pcs			
3	Supply and fitting of 150.Ah Lead Acid Battery @10C . 12VDC as per attached	6	Nos			
4	Supply and fitting TUV certified twin core solar DC cable of 10 sq. mm.	195	Rm			
5	Supply and fitting 2.5 mm PVC insulated	4	Roll			
6	Supply and fitting Double Pole AC MCB of 16 A; NS Standard.	3	Nos			
7	Supply and fitting Double Pole DC MCB of 16 A; NS Standard.	3	Nos			
8	Supply and fitting Copper Earthing Wire of 10 sq. mm PVC insulated NS Standard Copper Wire.	185	Rm.			
8	Supply and fitting of Aluminium/GI Module Solar Panel Mounting Structure with Nuts bolts	12	Set			


 Kalyandehara Panchayat Municipal Executive
 Office of the Panchayat Municipal Executive
 Baidauli, Kalyandehara
 Lumbini Province, Nepal

 Chief Administrative Officer

	Supply, fitting and installation of Earthing system (Diameter copper clad Chemical (20 Kg) Earthing type)	3	Set				
	Transportation	1	Lumpsum				
	Installation, Testing and Commissioning of Charge of 2.4 kwp solar backup system with cable tie, nuts, bolts, clamps as as directed by engineer.	1	Set				
9	Installation, Testing and commissioning of charge of solar backup system 12 with cable tie, nuts, bolts, clamps, MCB and other required materials as directed by office	2	set				
Sub-Total Amount							
VAT @ 13% Sub-Total Amount							
Grand Total Amount							

The price shall include all customs duties and sales and other taxes already paid or payable on the components and raw material used in the manufacture or assembly of the item or the customs duties and sales and other taxes paid on the previously imported item offered ex warehouse, ex showroom, or off-the-shelf. These factors should not be entered separately.

Name of Contractor :
 Authorized Signature :
 Date :